



Project Example Glasgow Road, Waterfoot

Addressing the concerns of our customers

Our customer approached us to address some minor issues with the roof at the property, and ultimately to improve the look of the property.

Through consultation with our client we were able to recommend the Marley Major Old English red concrete roof tiles to provide them with the look they desired.

Minimising disruption

Our working methodology was developed to minimise disruption to the owner during the works. We adopted a lift system for material delivery of materials to the scaffold and a chute for all waste generated. By adopting this approach we minimised foot traffic too and from the working area throughout the works.



Scope of works

The project was programmed to take a total of 2 weeks from mobilisation to completion.

A scaffold was erected to the full perimeter of the property to provide safe access at all times. To ensure we understood the needs. Our qualified team of experienced roofers delivered the following:

- Strip off the existing roof covering from main roof and remove from site
- Supply and install a new breathable roofing membrane
- Strip out all existing leadwork and replace with new code 5 sheet lead
- Replace the flat roof dormer at rear of the property with built up flet roof system
- Supply and install new counter and tile battens
- Tile over roof with new Marley Major old English dark red concrete interlocking tiles.
- Supply and install new dry ridge & hip system complete with new Marley old English dark red concrete ridge tiles.

Quality First Time

Giving our customers peace of mind, we provide Qualitymark Protection and insurance backed guarantee protection on all of our works.